

Bridge Deck Replacement at Various Locations in The City of Rochester and Towns of Gates and Bloomfield, New York

General Project Description:



As part of the Accelerated Bridge program, Phase 1A, Contract 8, the NYSDOT replaced bridge decks on the following bridges.

BIN 1001830, NYS Route 5 over Mud Creek, Town of E. Bloomfield, Ontario County

BIN 1048600, Paul Road over Interstate 490 WB, Town of Chili, Monroe County

BIN 1050139, Inner Loop (940T) over Ramp LB, City of Rochester, Monroe County

BIN 1052160, Clinton Avenue over NYS Route 104, City of Rochester, Monroe County

BIN 1095550, Paul Road over Interstate 490 EB, Town of Chili, Monroe County

Ravi Engineering & Land Surveying, P.C. provided survey stakeout services as part of this project. Our scope of work included review of construction documents, locating existing field control and performing control adjustments. We also set additional project benchmarks and horizontal control and layout of project baselines. Layout grades and locations were provided for curbs, sidewalks, approaches, bridge decks, backwalls, piers and new earthwork. In addition, we created as-built drawings of existing conditions.

